

BHARAT SANCHAR NIGAM LIMITED
O/o THE Executive Engineer (Civil)
BSNL Civil Division, ALTTTC, Ghaziabad

NIQ No. : 04 /2021-22/EE/BCD/GZB/

Date : 22.03.2022

NOTICE INVITING QUOTATIONS

The wax sealed item rate quotations are invited by the Executive Engineer (Civil), BSNL Civil Division, ALTTTC, Ghaziabad, on behalf of CMD, Bharat Sanchar Nigam Limited for the work of **Urgent Misc. Plumbing and Sanitary work in 10 Rooms of Raman Hostel ALTTTC Ghaziabad during 2021-22**. The Vendors / Agencies are requested to submit their offer / quotations on the Schedule of Quantities to be obtained from the O/o The Executive Engineer (Civil), BSNL Civil Division, ALTTTC, Ghaziabad up to 11.00 AM on 24/03/2022. The schedule of Quantities can also be downloaded from website www.upw.bsnl.co.in/civil linked with this NIQ.

The wax sealed envelope containing "**Quotations**" will be received up to **15.00 Hours on 24/03/2022** in the office of The Executive Engineer (Civil), BSNL Civil Division, ALTTTC, Ghaziabad and will be opened at **16.00 Hours on the same date**.

The quotation sealed envelope with following informations written on it :

- 1) Name of work :
- 2) Last date of receipt of quotation
- 3) **Estimated Cost : Rs. 94,568/-**

Note ---

- 1) The quotation must be in sealed cover.
- 2) The Work should to be carried out as per CPWD Specification 2009 with up-to-date correction slip.
- 3) The time of completion of work will be 15 (**Fifteen**) Days.
- 4) Recoveries viz / Income Tax, water charges, Building Welfare Cess etc., will be made as per existing Govt rules.
- 5) Following documents are to be required to be submitted along financial quote.
 - (a) The Copy of proof for GST Registration / GST No.
 - (b) Copy of PAN No

Time Allowed for Completion : 15 (Fifteen) Days

Eligibility :

1. The enlisted contractors of DOT / BSNL Civil Wing and those of UP State PWD (Building works only), DOP, CPWD, MES and Railways having valid **EPF with ESI & GST registration** are eligible for this work:
2. The Scheduled time for carrying the work shall be 15 (Fifteen) Days from the date of issue of work order.
3. The Rates quoted shall be inclusive of all the taxes, GST, Octroi, loading / unloading, transportation as applicable etc. all complete, which is to be borne by the agency as per prevailing Rule.
4. The agency may note that they are liable for payment of GST as per Govt. of India Rules. Hence the rate should be inclusive of GST as applicable as per notification issued by Ministry of Finance, Govt. of India.

Executive Engineer (Civil)
BSNL, Civil Division,
ALTTTC, Ghaziabad

No. : **BSNL / NIQ / BCD / ALTTTC / GZB / 2022 /**

Date : **22 /03/2022**

Copy to :

1. The Sr. Chief Engineer (Civil), BSNL, UP (West) Civil Zone, Meerut.
2. The Superintending Engineer (Civil), O/o the Sr. Chief Engineer (C), BSNL UP (W) Civil Zone, Meerut.
3. The PPS to CGM, ALTTTC, Ghaziabad.]
4. The Account Officer (C/E), BSNL, Civil Division, ALTTTC, Ghaziabad.
5. The SDE (Civil), BSNL Civil Sub-Division-I and II, ALTTTC, Ghaziabad.
6. Notice Board.

SCHEDULE OF QUANTITIES

Name of the work : Urgent Misc. Plumbing and Sanitary work in 10 Rooms of Raman Hostel ALTTC Ghaziabad during 2021-22.

SN	Description of Item	Qty	Rate (Rs)	Unit	Amount (Rs)
1	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	5		One Cubic Metre	0
2	Cleaning of terrace/loft water storage tank (inside surface area) upto 2000 litre capacity at all heights with coconut brushes, duster etc., removal of silt, rubbish from the tank and cleaning the tank with fresh water disinfecting with bleaching powder @ 0.5gm per litre capacity of tank, including marking the date of cleaning on the side of tank body with the help of stencil and paint and disposing of malba, all complete as per direction of Engineer-in-Charge. (The old date already written on tank should be removed with paint remover or black paint and if date is not written with the stencil or old date is not removed deduction will be made @ Rs. 0.10 per litre if during cleaning any GI fittings or ball cock is damaged that is to be repaired by contractor at his own cost and nothing extra will be paid on this account)	5000		One Litre	0
3	Dismantling W.C. Pan of all sizes including disposal of dismantled materials i/c malba all complete as per directions of Engineer-in- Charge.	10		Each	0
4	Credit to unserviceable brass /cp brass fittings .	5		One Kilogram	0
5	Credit to MS/GI items.	5		One Kilogram	0
6	Cartage of Hydrogen gas cylinder for cleaning of choked water pipe line by pressure all complete as per direction of engineer in charge (Note: Labour shall be covered in the relevant agreement item.)	2		One Job	0
7	Cleaning of drainage manholes and sewer lines by removing the deposited and other rubbish from the manholes and cleaning the sewer lines by rodding and flushing with water as directed by the Engineer -in- charge. (Rate per One manhole and sewer line to next manhole)	4		Each	0
8	Supply of Assistant plumber / Assistant Carpenter or Beldar for helping of plumber/ Carpenter in plumbing works/ Carpentry work etc or to attend minor plumbing / carpentry problems as and when required for ALTTC compound as per direction of Engineer in charge.(Payment of plumber, if engaged, should be paid seperately in relavent items)	8		per day	0
9	Removing blockage of W.C Seat/ Nanani trap/ Floor trap & from associated pipes if any etc. by rodding /acid all complete as per direction of Engineer-in-charge.	10		Each	0
10	Providing various sanitary/ water supply fittings/ items of approved and ISI quality as decided by the Enginner in charge for day to day maintenance works. (Note: Labour shall be covered in the relevant agreement item.)				
a	B) White solid plastic seat with lid for pedestal type W.C pan complete	10		Each	0
11	Providing and fixing white vitreous china pedestal type (European type/ wash down type) water closet pan.	10		Each	0
12	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to Eueropean type W.C. of quality and make as approved by Engineer - in - charge.	10		Each	0
13	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete.				
a	10 litre capacity - White	10		Each	0
14	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	4		Each	0

15	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. : Internal work - Exposed on wall				
a	20 mm nominal outer dia. Pipes.	15		One Running Metre	0
b	25 mm nominal outer dia .Pipes.	10		One Running Metre	0
16	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	2000		One Litre	0
17	Providing and fixing PTMT bib cock of approved quality and colour.				
a	15 mm nominal bore, 122 mm long. Weighing not less than 99 gms.	5		Each	0
18	Providing and fixing PTMT pillar cock of approved quality and colour .				
a	15mm nominal bore, 107 mm long. Weighing not less than 110 gms.	10		Each	0
19	Providing and fixing PTMT grating of approved quality and colour.				
a	Circular type.				
i	100 mm nominal dia.	20		Each	0
20	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour.				
a	15 mm nominal bore with 30 cm length.	20		Each	0
21	Repairing of CP brass Bib cock, Stop cock, Pillar cock, Angle valve with providing new brass phase,washer etc,all complete as per direction of E-I-C .	15		Each	0
		Total			

Executive Engineer (Civil)
BSNL, Civil Division,
ALTTC, Ghaziabad